

University and Fourth roadway improvements

Minneapolis Pedestrian Advisory Committee Engineering Subcommittee – June 17, 2021



Introductions

Project team

- Hennepin County
 - Kelly Agosto project manager
- Design team
 - Steve Weser design consultant project manager





Project status update



- Previous outreach
- Agency coordination and goals
- Engagement phase 2 alternatives
- Constraints / challenges



Design decisions



- Number of travel lanes
- Partial reconstruction planned
- Preference for street level curb separated bike facility
- Avoid features in right-of-way (mature trees, historic fence/wall)
- Transit and pedestrian improvements




Layout A (two-way bikeway on University Ave)


- Conceptual, not engineered yet
- Two-way curb separated bike facility on University Avenue 10th Ave to Oak St
- One-way buffered bike lane on 4th Street minimal approach
- Partial construction focused on one side
 - Utilize existing infrastructure along each street where appropriate
- Limited opportunity for above ground stormwater management, enhanced buffer space, and green space



• University Ave – west of 17th Ave / Church St





• University Ave – east of 17th Ave / Church St





• 4th Street – west of 17th Ave







typical section





• 4th Street – east of 17th Ave








example photo



Hennepin County

Bike signal phasing

- Leading interval for bikes and pedestrians (4 seconds)
 - Vehicle and bike volume peaks do not coincide
- "NO TURN ON RED" signs
 - Minimizes conflicts with contraflow bikers








Layout B (one-way bike facilities on each street)


- Conceptual, not engineered yet
- One-way buffered bike lane on University Ave and 4th Street
- Partial construction focused on one side
 - Utilize existing infrastructure along each street where appropriate
- Slightly more area for above ground stormwater management, enhanced buffer space, and green space



• University Ave – west of 17th Ave / Church St




• University Ave – east of 17th Ave / Church St




typical section




• 4th St – west of 17th Ave








• 4th St – east of 17th Ave











IDENTICAL TO LAYOUT A
IN THIS SEGMENT

Next steps

- Public feedback
 - Online open house June 2021
- Stakeholder outreach
- Preferred layout
- Municipal consent August 2021
- Final design complete June 2022
- Construction 2023





Kelly Agosto

kelly.agosto@hennepin.us, 612-596-0365

Project manager for design Hennepin County

Steve Weser

sweser@alliant-inc.com, 612-767-9347

Design consultant project manager Alliant Engineering, Inc.



Project website hennepin.us/ universityandfourth



Discussion and questions



